



SPECIFICATION:21/2019-2020
Purchase and delivery of MV and LV Overhead LINES Material

Background:

This is to obtain material to do repair and maintenance in Senqu Municipality area in order to supply a reliable network to ensure that our Customers has constant Electricity supply without un-necessary breakdowns and power delays.

Description of Specifications: Purchase and delivery of MV and LV Overhead LINES Material

Measurement Unit (If Applicable)	Quantity	Actual Specifications	Further Details (If required)	Price (Inclusive of Vat) Year 1	Price (Inclusive of Vat) Year 2	Price (Inclusive of Vat) Year 3
Each	1	Air-Dac Strain Grips				
Each	1	Air-Dac Suspension Clamp				
Each	1	Arrestors Lightning	24 KV			
Each	1	Bow Shackle	70kN			
Each	1	Brazing Strap	50 x 6 x 910 (mm)			
Each	1	Bundle ABC	Suspension Hangers			
Each	1	Bundle ABC	Grips - Bare (Blue)			
Each	1	Bundle ABC	Grips - Insulated (Black)			
Each	1	Bundle ABC	Strain Bracket			
Each	1	Bundle ABC	Suspension Bracket			
Each	1	Drop Out Fuses	24 KV Holders complete Unit			
Each	1	Fuse Links 22KV	3A			
Each	1	Fuse Links 22KV	5A			
Each	1	Fuse Links 22KV	10A			
Each	1	Fuse Links 22KV	15A			

Each	1	Fuse Links 22KV	30A			
Each	1	Fuse Links 22KV	40A			
Each	1	Fuse Links 22KV	60A to 65A			
Each	1	Fuse Links 22KV	80A			
Each	1	Fuse Links 22KV	100A			
Each	1	IPC Clamps	25-95mm ² Main, 25-95mm ² Tap (Black - Insulated)			
Each	1	IPC Clamps	35-95mm ² Main, 6-25mm ² Tap (Blue - Bare)			
Each	1	IPC Clamps	35-95mm ² Main, 6-25mm ² Tap (Black - Insulated)			
Each	1	IPC Clamps	50-240mm ² Main, 50-240mm ² Tap (Black - Insulated)			
Each	1	Lightning Arrestors 10KN	24kV			
Each	1	Lightning Arrestors	6kV Neutral			
Each	1	Line Post Insulators 10KN	22kV			
Each	1	Line Post Insulators 4kN	6KV			
Each	1	Long Rod Insulators (Tongue & Clevis)	22KV			
Each	1	P G Clamps	Bi-Metal. 4-15mm ² Main, 4-15mm ² Tap			
Each	1	Pigtail Hook	M10 x 350 mm			
Each	1	Pigtails Bolts	M16 x 350 mm			
Each	1	Pistol Grips - Strain Clamps	Strain Clamps for MV - Gopher to Hare Conductor			
Each	1	Pole Brackets - Question Mark	To Install Drop-Out fuse Bases onto X - Arm			
Each	1	Pole Top Bracket	To Install Post Insulator on Top of pole			
Each	1	Preformed Products	Full Tension Splice for Mink			

21/2019-2020 Purchase and Delivery of MV and LV Overhead LINES Material

Each	1	Preformed Products	Full Tension Splice for Gopher			
Each	1	Preformed Products	Side Ties for Mink			
Each	1	Preformed Products	Side Ties for Gopher			
Each	1	Preformed Products	Top Ties for Mink			
Each	1	Preformed Products	Top Ties for Gopher			
Each	1	Preformed Products	Stay Guy Grip for 7x4mm ² Stay Wire			
Each	1	Preformed Products	Stay Guy Grip for 3x3,35mm ² Stay Wire			
Each	1	Preformed Products	Pole Top Make Off - 7x4mm ² (Green)			
Each	1	Preformed Products	Pole Top Make Off - 3x3,35mm ² (Black)			
Each	1	Preformed Products	Dead End for Mink			
Each	1	Preformed Products	Dead End for Gopher			
Each	1	Preformed Products	Armour Rods for Mink			
Each	1	Preformed Products	Armour Rods for Gopher			
Each	1	Spindle for Post Insulators	M20 x 300mm			
Each	1	Spindle for Post Insulators	M20 x 50mm			
Each	1	Stay	Insulator - Porcelain - 22kV 110kN			
Each	1	Stay	Wire - 7 x 4mm ²			
Each	1	Stay	Wire 3 x 3,35mm ²			
Each	1	Stay	Stay Wire Thimble			
Each	1	Stay	Stay Rod - M20 x 2400mm Adjustable			
Each	1	Stay	Stay Rod - M16 x 1800mm			
Each	1	Stay	Stay Plate - Octagonal M20 300mm Diameter			